



SPACE DESIGN LOAD SUMMARY

2026-09-27

Bathroom_2

Level: Level 0 · Internal condition: TM59_Bathroom

DESIGN CRITERIA

	Heating	Cooling
Room set point	16.0 °C	150.0 °C
Outdoor dry bulb	—	—
Outdoor RH (coincident)	—	—
ROOM HUMIDITY		
Humidification set point	—	
lower RH limit		
Dehumidification set point	—	
upper RH limit		

SIZING (TAS DESIGN LOADS)

	Heating	Cooling
Design load	0 W	0 W
Design load per area	0.0 W/m²	0.0 W/m²
Sizing multiplier	not set	not set
Design loads: from Tas sizing — date/currency not recorded		

HEATING

Design day	Leeds_TRY ANN HTG 100% CONDS DB	
	Design day	Full year
Peak load	1,140 W	104 W
Peak hour	23:00–24:00	23 Dec 09:00–10:00
Room dry bulb	16.0 °C	16.0 °C
Room resultant	13.9 °C	15.9 °C
Room RH	20 %	35 %
Room humidity ratio	2.2 g/kg	3.9 g/kg
Outdoor dry bulb	—	-2.3 °C
Outdoor RH	—	100 %

SENSIBLE COMPONENTS AT PEAK

Component	Design day (W)	Full year (W)
Infiltration / ventilation	-112	-93
Building heat transfer	-1,023	-3
External conduction — opaque	-5	-7

Zero at both peaks (not listed): Solar, Lighting, Occupancy (sensible), Equipment (sensible), Air movement (inter-zone), External conduction — glazing, Air handling unit, Occupancy (latent), Equipment (latent)

Components as the simulation reports them at each peak hour: + gain to the room air, – loss from it. No total is derived.

COOLING

Design day	Leeds_TRY ANN CLG 0% CONDS DB=>GRad	
	Design day	Full year
Peak load	0 W	0 W
0 W: no cooling demand on the design day or over the full year, so no peak hour, room or outdoor state or component breakdown.		

RESULTS

	Heating	Cooling
Status	Available	Available
Result source	SAM.Analytical.Tas	SAM.Analytical.Tas
Read into model	27 Sep 2026 20:42	27 Sep 2026 20:42
Matches current model	not recorded	not recorded

Peak hour: a design-day peak has an hour of the day only, no date; a full-year peak shows day and hour, no year.

Design loads (sizing) and simulated peaks are shown side by side for information; no acceptance rule is applied.